

Contents

I	Introduction	3
II	Material and methods	6
1	Theoretical backgrounds	6
2	Study area: an overview of the station	6
3	Material and instruments	6
3.1	<i>In situ</i> : the Multiband albedometer	6
3.2	<i>In situ</i> : the Solalb albedometer	8
3.3	<i>In situ</i> : automatic weather stations (AWS)	8
3.4	Satellite imagery: Sentinel-3 Ocean Land and Colour Instrument	8
3.4.1	Generalities	8
3.4.2	Data availability	8
4	Methods	8
4.1	Processing of Multiband data	8
4.1.1	Overview of the existing algorithm	8
4.1.2	New implementations	10
4.2	Processing of Solalb data	10
4.3	Processing of S-3 OLCI data	10
4.3.1	Implementation of SICE 1.6 utilities	10
4.3.2	Diagnostic techniques	10
III	Results	10
5	Atmospheric conditions: emissivity analysis	10
6	Time series from Multiband and S-3 OLCI	10
7	Diagnostic of the results for EAIIST stations	10
7.1	Multiband issues	11
7.2	OLCI issues	11
7.2.1	OLCI and Solalb: a comparison	11

IV Discussion	11
8 Considerations on the performance of the instruments	11
9 Geoscientific interpretation of the time series	11
V Conclusion	11
References	11

I Introduction

Snow is one of the major component of the cryosphere. Its global distribution on both ocean and land areas strongly depends on seasonality, latitude, and elevation. It occurs in three forms, mainly: permanent snow on ice sheets and glaciers, snow on sea ice, and seasonal snow cover. The latter is estimated to account for 1.3% (summer) to 30.6% (winter) of the Northern Hemisphere land surface (Vaughan et al., 2013), with the 1967–2026 mean snow cover extent (SCE hereafter) in winter being around $39.79 \times 10^6 \text{ km}^2$ (Robinson & Estilow, 2012). Sea ice is almost completely covered by snow during the winter season; its peak concentration, therefore representative of sea ice specific SCE, occurs in March in the Northern Hemisphere ($15.03 \times 10^6 \text{ km}^2$) and in September in the Southern Hemisphere ($18.61 \times 10^6 \text{ km}^2$) (Fetterer et al., 2025; Warren et al., 1999). Finally, perennial snow mean extent over the 2000–2022 period is estimated at $16.47 \times 10^6 \text{ km}^2$ from NASA's Moderate Resolution Imaging Spectroradiometer (MODIS), including glaciers, ice caps, Greenland and Antarctica ice sheets (Johnston et al., 2024).

These several tens of millions of snow-covered squared kilometres play a major role in freshwater resources availability, ecosystems equilibrium and, particularly, climate regulation. In fact, among its many physico-chemical properties, snow represents one of the strongest reflective materials on Earth's surface. The fraction of solar radiation delivered to a body that is diffusely reflected by it is called *albedo*; for snow, this amount is roughly close to 1, since its highest reflectivity occurs in the range of visible light, *i.e.* where solar radiation intensity peaks (Kokhanovsky & Zege, 2004). Thanks to its high albedo, snow represents of the main contributors to Earth's energy budget regulators (National Snow and Ice Data Center, 2024). Of the 340 W m^{-2} of net solar radiation incident at the top of the atmosphere, Northern Hemisphere land snow cover alone reflects approximately 2 W m^{-2} back to space, averaged over the 1979–2008 period; in May, when SCE and soil insulation are highest, this quantity can reach 4.5 W m^{-2} (Flanner et al., 2011). Without the year-average radiative forcing from land snow cover alone, Earth's surface temperature would be approximately 0.54 K higher than the current planetary mean. This estimate follows from linearising the Stefan-Boltzmann law with respect to temperature, assuming that Earth radiates as a blackbody with no feedback effects, making it a lower-bound estimate. In fact, real climate feedbacks (water vapour, lapse rate, clouds) reduce the effective restoring force, amplifying the true temperature response (Cronin & Dutta, 2023).

As the whole cryosphere in general, snow distribution on Earth is undergoing dramatic changes because of the current anthropogenic perturbation of the climate system and warming of the atmosphere. At the global scale, SCE is experiencing a negative trend since the 1980s, with a statistically significant reduction in the mean area of 5% after 1988, compared to the 1967–1988 period, in the Northern Hemisphere only, and an earlier melt onset in the spring season (Dye, 2002; Robinson & Frei, 2000). Less snow cover in both space and time, driven by rising temperatures, reduces terrestrial albedo and increases the absorption of incoming

solar radiation at the surface, which in turn amplifies warming (Cubasch et al., 2001; Holland & Bitz, 2003). This mechanism is known as the positive snow– albedo feedback: it is estimated to be responsible of a reduction in Northern Hemisphere land snow cover radiative cooling forcing of $\sim 0.22 \text{ W m}^{-2}$ from 1979 to 2007, which nearly equals the contribution of Arctic sea ice (Flanner et al., 2011). The magnitude of such feedback is further amplified when light-absorbing particles, such as dust, black carbon and microbial growth, deposit on the surface of snowpack (Skiles et al., 2018).

It is clear, at this point, that developing a proper understanding of how snow interacts with solar radiation is crucial for a better understanding of the evolution of the climate system. Snow optical properties, particularly albedo, are directly related to density and grain type, and are strongly wavelength-dependent (Bohren & Barkstrom, 1974; Kokhanovsky & Zege, 2004). Quantifying these properties involves radiative transfer calculations extended to the uppermost part of the snowpack, which must be assumed to be composed of individual grains of a given size and shape. Many studies have adopted equivalent spheres, assuming they can properly represent any other shape at a given optical diameter (Bohren & Barkstrom, 1974; Warren et al., 1999). However, recent studies demonstrated that this approach is not satisfactory when it comes to specific properties such as the single-scattering albedo – the fraction of intercepted radiation that is scattered rather than absorbed – and the bidirectional reflectance distribution function (BRDF) – the reflectance of a surface for a specific combination of illumination and viewing directions (Dumont et al., 2010; Kokhanovsky & Zege, 2004; Libois et al., 2013). For this reason, when addressing grain size, a more general, shape-independent quantity is preferable to the optical diameter: the *specific surface area* (SSA), defined as the total surface area of snow grains per unit mass – expressed in $\text{m}^2 \text{ kg}^{-1}$ (International Union of Pure and Applied Chemistry (IUPAC), 2025). This quantity, used hereafter to address snow grain size, largely influences snow reflectance for wavelengths in the Near-Infrared (NIR) range, between 750 nm and 1400 nm particularly (Warren & Wiscombe, 1980). For example, a factor-6 decrease in the SSA (e.g. from 60 to $10 \text{ m}^2 \text{ kg}^{-1}$) can approximately reduce albedo of 15% at 1000 nm. In general, albedo decreases monotonically with SSA and can be modelled as an exponential function of $\text{SSA}^{-1/2}$ (Kokhanovsky & Zege, 2004).

Snow grain size dynamics are therefore a key indicator of how snowpack optical properties evolve over time and space, making their tracking essential. Changes in grain size are primarily driven by processes such as metamorphism, wind drift, and precipitation.

When transformations in size and shape occur below the melting point ($T = 0^\circ\text{C}$), the metamorphism is dry: the grain size grows at a rate defined by the respective increase in temperature and temperature gradient (Colbeck, 1982). Instead, if snow is at the melting point, the liquid water content directly drives the size increase, which is faster than in the dry case – we talk about wet metamorphism, in this case (Wakahama, 1968). Anyway, independently of the type of metamorphism, the change in size is always positive and irreversible (**find a cit**).

Transportation by the wind occurs when its velocity breaks snow cohesion and lifts grains. This is more likely

for fresh-fallen snow than for old, metamorphosed snow (Lenaerts et al., 2017). This process, called wind drift, varies with wind speed: saltation occurs under weak winds, with snow skipping a few centimeters above the surface, while stronger winds create snow plumes, lifting grains up to hundreds of meters – the so-called blowing snow (Adok, 1977; World Meteorological Organization, 2024). Wind drift has two opposing effects on grain size. Erosion of the snowpack's upper layers exposes older, coarser, and less reflective layers (Lenaerts et al., 2017). Conversely, wind fractures grains through collisions, so newly formed deposits typically consist of finer grains (Domine et al., 2009).

Snow fall is generally responsible of depositing fresh and more fine-grained snow at surface, potentially covering already metamorphosed and coarser layers, thus increasing SSA and albedo (Domine et al., 2009).

This study is focused on the temporal evolution of snow and its albedo over the whole Antarctica, where all the processes of above act and interplay in a complex manner, over a wide range of climatic and geographical contexts. The Antarctic Ice Sheet (AIS), expanding for $14 \times 10^6 \text{ km}^2$ over 98% of the continent, is almost completely snow-covered year-round. As a polar region, it plays a massive role in positive climate feedback. At the same time, compared to the Arctic, Antarctica presents unique challenges for the exploration of surface radiative properties.

Being such a harsh and inaccessible place, it has only allowed *in situ* investigations limited to regional scales and relatively short time coverage. This has led the scientific community to rely on satellite data, which inherits higher uncertainties and reduced spatio-temporal resolution, from missions such as AVHRR, MODIS, and CLARA-A2.1-SAL (sunChangesAntarcticsSummer2023; Calleja et al., 2019).

Moreover, many of the AIS surface processes are not yet properly understood, particularly toward the center of the ice sheet. One of these is the mechanism involved in the formation of snow megadunes. These are antidune-like sedimentary forms, whose fields cover a large fraction of the central part of the AIS ($500 \times 10^5 \text{ km}^2$) (Frezzotti et al., 2002). They have relatively small amplitudes (1–8 m), compared to their wavelength (2–4 km), and crest lengths of 10 to 100 km (Fahnestock et al., 2000)—these characteristics prevented their observation until the beginning of satellite exploration over the continent. Their formation likely results from a complex interplay between geomorphological and meteorological conditions that causes a cryosphere-atmosphere feedback mechanism: katabatic winds, blowing toward the outer boundaries of the AIS from the center, affect local topography by deposition-erosion processes. Topography, in turn, modifies the katabatic wind field; megadunes develop perpendicularly to the main direction of such winds (<empty citation>). Still, the way snow grain size evolves on these structures remains an unexplored topic.

With this work, we aim to improve the understanding of surface albedo evolution in Antarctica by combining *in situ* measurements with satellite observations. Using data from automated albedometers installed at several locations on the AIS, we will produce time series of locally measured specific surface area (SSA) and compare them with satellite-retrieved grain size. Measurement stations were deployed in two primary locations: on the coast near the French station Dumont d'Urville, and in a megadune field, with one

albedometer on the erosion area and another on the accumulation area of a dune.

The overarching goals of this analysis are:

- to validate a satellite product, ESA's Sentinel-3 Ocean and Land Color Instrument, enabling long-term and continent-wide studies of snow albedo at a relatively fine resolution (~ 300 m), compared to other missions (e.g., MODIS);
- to deepen the understanding of processes driving temporal albedo changes at the local scale, particularly on megadunes, using an unprecedented 6-year continuous *in situ* record of snow albedo.

The analysis is structured as follows:

1. **Processing of *in situ* data:** upgrading and optimizing the existing workflow developed by Arioli et al., 2023; this includes both processing data from the main instrument (Multiband and relative weather stations) and from Solalb, a second albedometer used as an external reference to assess the quality of Multiband and Sentinel-3 performances;
2. **Processing of Sentinel-3 data:** downloading the frames and executing the SICE 1.6 algorithm, as described by Kokhanovsky et al., 2019;
3. **Comparison of the time series:** performing corrections to address possible gaps between the two datasets and interpreting the retrieved albedo dynamics geoscientifically.

II Material and methods

1 Theoretical backgrounds

!!! This risks to become "textbook"-like - then, must be SUPER ADAPTED TO MY SPECIFIC GOAL AND BE VERY PERSONAL AND NOT GENERAL AT ALL - PASSIONATING ! write it after matmethods and results

2 Study area: an overview of the station

3 Material and instruments

3.1 *In situ*: the Multiband albedometer

The main instrument used in this study is the Multiband albedometer, developed at Grenoble's Institute for Geosciences of the Environment (IGE) and fully described in Arioli et al., 2023. It is a robust automated optical radiometer capable of acquiring solar radiation across a discrete set of bands, from the visible to the short-wave infrared, which are essential for retrieving snow surface albedo. Similar to previously developed albedometers (e.g., Autosolex, Solalb; see Picard et al., 2016), the Multiband consists of a set of metal gantries. One perfectly leveled pole projects the instrument head horizontally at ~ 3 m from the installation




Figure 1: Structure of Multiband | Long caption

point and at a height of ~ 2 m above the snow surface, typically oriented north- or southward to minimize shadowing from other components. The head features two custom cosine-shaped light collectors, one pointing upward and the other downward, to measure incident and reflected irradiance, respectively. These collectors, meticulously designed by Picard et al., 2016, incorporate a bumped Teflon surface to maximize performance at any solar zenith angle (SZA), including grazing angles, which are critical for accurate radiation measurements.

The signal is transmitted to the instrument's recording unit via two Ocean Optics QP800-VIS-NIR optical fibers, each 6 m long with a $800\text{ }\mu\text{m}$ core diameter. Unlike earlier albedometers, where optical fibers directly sent the signal to a spectrometer for high-resolution (3 nm) spectral recording, the Multiband employs a more energy-efficient approach. The broadband radiation transmitted by the fibers passes through a set of polarizing filters mounted on a ~ 20 cm wheel with 12 slots. These filters are Edmund Optics' TECHSPEC® hard-coated optical density (OD) 4.0, 25 nm bandpass filters, specific for wavelengths of 500, 600, 800, 925, 1050, 1300, and 1550 nm. During a full measurement cycle (30 s), the wheel rotates to acquire spectral measurements for each selected wavelength from both the incident and reflected signals. These signals are transmitted to dual-band Silicon (Si) / Indium-Arsenide-Gallium (InGaAs) photodiodes (DSD2, Thorlabs). Measurements on the two channels are simultaneous, and the wheel includes duplicate filters to ensure synchronous recordings at the most relevant wavelengths, as well as one capped slot to measure the dark current (*i.e.* background thermal noise) – see Figure 1 for details. The signals registered by the dual photodiodes are amplified by a high-gain electronic board. Finally, a Campbell Scientific CR1000x data logger records the spectral radiation in mV. Since the duration of a full measurement cycle is long enough for atmospheric conditions to potentially change, a measure of ambient light is also recorded at every step: a third upward-facing optical fiber transmits incoming radiation to a Si photodiode (FDS100, Thorlabs). This photodiode acquires a wideband measurement in the 350–1100 nm range, referred to as the reference, expressed in light counts. Its signal undergoes the same voltage amplification and recording steps as the spectral measurements; for a single cycle, 12 references are registered.




Figure 2: Workflow of Multiband processing | Modified after Arioli et al., 2023

The entire system's electronics are powered by a solar panel. The Multiband has demonstrated its durability by acquiring continuous measurements without interruption at each of the stations where it was installed.

3.2 *In situ*: the Solalb albedometer

3.3 *In situ*: automatic weather stations (AWS)

3.4 Satellite imagery: Sentinel-3 Ocean Land and Colour Instrument

3.4.a Generalities

Orbit, resolution, swath, revisit time etc.

3.4.b Data availability

4 Methods

4.1 Processing of Multiband data

4.1.a Overview of the existing algorithm

The pipeline for processing Multiband data is summarized in Figure 2 and builds on the work of Arioli et al., 2023. It executes functions from a custom Python library specifically developed for this purpose (the `generic_algorithm`), along with utilities from the open-source module `snowoptics` (GitHub), a library for retrieving snow optical properties based on the Asymptotic Radiative Transfer theory (ART, Kokhanovsky and Zege, 2004). This processing had already been applied to measurements acquired by all three Cap Prud'Homme stations (D5, D10, D17) until 2022 in Arioli et al., 2023's work.

1. Raw data filtering

A preprocessing step excludes low-quality data, including: (i) measurements acquired at $\text{SZA} > 70^\circ$ due to the limited performance of cosine collectors at low solar angles; (Picard et al., 2016); (ii) measurements acquired under varying or low ambient light conditions, if the standard deviation of the 12 references recorded during a cycle exceeds 1% of their mean radiance; and (iii) all records at 1550 nm due to the poor signal-to-noise ratio.

2. Dark current

The measurements are corrected for the background thermal noise of the photodiodes. Four dark currents are registered at every cycle (Si and InGaAs, for both the incident and reflected channels) and subsequently subtracted from the respective channel's spectral irradiance.

3. Cross-calibration

The incident and reflected signals passing through the cosine collectors and the optical fibers naturally differ due to varying transmissivity and sensitivity of the components in the two channels. To account for this, a parallel cross-calibration is performed during the installation of the albedometers. This involves orienting both light collectors upward and side-by-side to record the same irradiance over two days at an hourly resolution (every 10 minutes at solar noon). The two signals are then corrected following steps 1 and 2 of the current processing chain, averaged, and their ratio is multiplied by every incident spectrum measured during the operational stage of the albedometer to compensate for differences in the electronic response of the two channels.

4. Cosine response correction

Each light collector behaves uniquely at different solar angles under perfectly direct light conditions, with its response always diverging by a given amount from an ideal cosine curve. For this reason, before deployment in the field, every collector's response is calibrated in the lab by illuminating it with a direct light beam at different angles. This experimental response is used to normalize every measurement. Since this correction step only involves the direct component of the incident radiation – not its diffuse part or the fully diffused reflected light – the direct-to-diffuse light ratio must be quantified for every measurement. This ratio depends on: (i) atmospheric characteristics at the specific geographical location (longitude, latitude, altitude); (ii) solar elevation, *i.e.* the SZA; and (iii) meteorology at the time of the measurement, particularly cloud cover. To account for the first two factors, a time-independent, direct-to-diffuse partitioning is simulated using the Santa Barbara DISORT Atmospheric Radiative Transfer (SBDART) model (Ricchiazzi et al., 1998). Cloud cover is quantified using the 30-minute resolution recordings of the AWS located near the albedometers, with the methodology proposed by Marty and Philipona, 2000. These two steps will be detailed later.

5. Albedo calculation

The ratio between the corrected incident and reflected records yields a first spectral albedo, $\alpha(\lambda)$, which, at this stage, is assumed to be for a plane and flat surface. Values of $\alpha < 0$ and $\alpha > 1.5$ are discarded.

6. Slope correction

Albedo is then corrected for potential slope and surface irregularities (*e.g.* sastrugi) characterizing the snow surface on the day of the measurement, following Picard et al., 2020. The custom function `generic_algorithm.albedo_timeseries_correction` is used to iteratively compute the unknown slope parameters that best fit the within-day evolution of the previously retrieved albedo spectra. At the end of this step, a daily averaged, slope-corrected albedo spectrum is produced.

7. SSA estimate

Kokhanovsky and Zege, 2004's ART theory is finally used to compute the snow grain size (SSA) from the daily albedo, as previously described in the theoretical background section.

4.1.b New implementations

We extend the pipeline to the latest 2026 records and to the two stations installed on a megadune during the 2019 EAIIST campaign.

Direct-to-diffuse light ratio

Clear Sky Index (CSI)

Diagnostic techniques

- Calibration files
- Inclinator time series
- Sub-daily variability in the signal

4.2 Processing of Solalb data

4.3 Processing of S-3 OLCI data

4.3.a Implementation of SICE 1.6 utilities

4.3.b Diagnostic techniques

III Results

5 Atmospheric conditions: emissivity analysis

CSI results ? Dir diff ?

6 Time series from Multiband and S-3 OLCI

DDU very cool, EAIIST not so very cool, then...

7 Diagnostic of the results for EAIIST stations

... then here we go




Figure 3: Apparent emissivity | Test figure

7.1 Multiband issues

7.2 OLCI issues

7.2.a OLCI and Solalb: a comparison

Do not simply list the results, it can be boring If the conclusion from a result is very fast, just put it in the results

IV Discussion

8 Considerations on the performance of the instruments

9 Geoscientific interpretation of the time series

Despite the imperfection of the results and the technical issues, some interesting interpretations about the signal recorded from both the *in situ* equipment and the satellite can be drawn.

V Conclusion

References

Adok, U. (1977). Snow Drift (2018/02/07). *Journal of Glaciology*, 19(81), 123–139. <https://doi.org/10.3189/S0022143000215591>

- Arioli, S., Picard, G., Arnaud, L., & Favier, V. (2023). Dynamics of the snow grain size in a windy coastal area of Antarctica from continuous in situ spectral-albedo measurements. *The Cryosphere*, 17(6), 2323–2342. <https://doi.org/10.5194/tc-17-2323-2023>
- Bohren, C. F., & Barkstrom, B. R. (1974). Theory of the optical properties of snow. *Journal of Geophysical Research (1896-1977)*, 79(30), 4527–4535. <https://doi.org/10.1029/JC079i030p04527>
- Calleja, J. F., Corbea-Pérez, A., Fernández, S., Recondo, C., Peón, J., & de Pablo, M. Á. (2019). Snow Albedo Seasonality and Trend from MODIS Sensor and Ground Data at Johnsons Glacier, Livingston Island, Maritime Antarctica. *Sensors*, 19(16), 3569. <https://doi.org/10.3390/s19163569>
- Colbeck, S. C. (1982). An overview of seasonal snow metamorphism. *Reviews of Geophysics*, 20(1), 45–61. <https://doi.org/10.1029/RG020i001p00045>
- Cronin, T. W., & Dutta, I. (2023). How Well do We Understand the Planck Feedback? *Journal of Advances in Modeling Earth Systems*, 15(7), e2023MS003729. <https://doi.org/10.1029/2023MS003729>
- Cubasch, U., Meehl, G., Boer, G., Ronald, S., Dix, M., Noda, A., Senior, C., Raper, S., & Yap, K. (2001). Projections of Future Climate Change.
- Domine, F., Taillandier, A.-S., Cabanes, A., Douglas, T. A., & Sturm, M. (2009). Three examples where the specific surface area of snow increased over time. *The Cryosphere*, 3(1), 31–39. <https://doi.org/10.5194/tc-3-31-2009>
- Dumont, M., Brissaud, O., Picard, G., Schmitt, B., Gallet, J.-C., & Arnaud, Y. (2010). High-accuracy measurements of snow Bidirectional Reflectance Distribution Function at visible and NIR wavelengths – comparison with modelling results. *Atmos. Chem. Phys.*, 10(5), 2507–2520. <https://doi.org/10.5194/acp-10-2507-2010>
- Dye, D. G. (2002). Variability and trends in the annual snow-cover cycle in Northern Hemisphere land areas, 1972–2000. *Hydrological Processes*, 16(15), 3065–3077. <https://doi.org/10.1002/hyp.1089>
- Fahnestock, M. A., Scambos, T. A., Shuman, C. A., Arthern, R. J., Winebrenner, D. P., & Kwok, R. (2000). Snow megadune fields on the East Antarctic Plateau: Extreme atmosphere-ice interaction. *Geophysical Research Letters*, 27(22), 3719–3722. <https://doi.org/10.1029/1999GL011248>
- Fetterer, F., Knowles, K., Meier, W. N., Savoie, M., Windnagel, A., & Stafford, T. (2025). Sea Ice Index, Version 4. <https://doi.org/10.7265/A98X-0F50>
- Flanner, M. G., Shell, K. M., Barlage, M., Perovich, D. K., & Tschudi, M. A. (2011). Radiative forcing and albedo feedback from the Northern Hemisphere cryosphere between 1979 and 2008. *Nature Geoscience*, 4(3), 151–155. <https://doi.org/10.1038/ngeo1062>
- Frezzotti, M., Gandolfi, S., & Urbini, S. (2002). Snow megadunes in Antarctica: Sedimentary structure and genesis. *Journal of Geophysical Research: Atmospheres*, 107(D18), ACL 1–1. <https://doi.org/10.1029/2001JD000673>
- Holland, M. M., & Bitz, C. M. (2003). Polar amplification of climate change in coupled models. *Climate Dynamics*, 21(3), 221–232. <https://doi.org/10.1007/s00382-003-0332-6>

- International Union of Pure and Applied Chemistry (IUPAC). (2025). Specific surface area. <https://doi.org/10.1351/goldbook.S05806>
- Johnston, J., Jacobs, J. M., & Cho, E. (2024). Global Snow Seasonality Regimes from Satellite Records of Snow Cover. *Journal of Hydrometeorology*, 25(1), 65–88. <https://doi.org/10.1175/JHM-D-23-0047.1>
- Kokhanovsky, A., Lamare, M., Danne, O., Brockmann, C., Dumont, M., Picard, G., Arnaud, L., Favier, V., Jourdain, B., Le Meur, E., Di Mauro, B., Aoki, T., Niwano, M., Rozanov, V., Korkin, S., Kipfstuhl, S., Freitag, J., Hoerhold, M., Zuhr, A., ... Box, J. E. (2019). Retrieval of snow properties from the Sentinel-3 Ocean and Land Colour Instrument. *MDPI Remote Sens.*, 11, 2280. <https://doi.org/10.3390/rs11192280>
- Kokhanovsky, A., & Zege, E. (2004). Scattering optics of snow. *Applied Optics*, 43(7), 1589–1602. <https://doi.org/10.1364/AO.43.001589>
- Lenaerts, J. T. M., Lhermitte, S., Drews, R., Ligtenberg, S. R. M., Berger, S., Helm, V., Smeets, C. J. P. P., Broeke, M. R. v. d., van de Berg, W. J., van Meijgaard, E., Eijkelboom, M., Eisen, O., & Pattyn, F. (2017). Meltwater produced by wind–albedo interaction stored in an East Antarctic ice shelf. *Nature Climate Change*, 7(1), 58–62. <https://doi.org/10.1038/nclimate3180>
- Libois, Q., Picard, G., France, J. L., Arnaud, L., Dumont, M., Carmagnola, C. M., & King, M. D. (2013). Influence of grain shape on light penetration in snow. *The Cryosphere*, 7(6), 1803–1818. <https://doi.org/10.5194/tc-7-1803-2013>
- Marty, C., & Philipona, R. (2000). The clear-sky index to separate clear-sky from cloudy-sky situations in climate research. *Geophysical Research Letters*, 27(17), 2649–2652. <https://doi.org/10.1029/2000GL011743>
- National Snow and Ice Data Center. (2024). What is the cryosphere? <https://nsidc.org/learn/what-cryosphere>
- Picard, G., Dumont, M., Lamare, M., Tuzet, F., Larue, F., Pirazzini, R., & Arnaud, L. (2020). Spectral albedo measurements over snow-covered slopes: Theory and slope effect corrections. *The Cryosphere*, 14(5), 1497–1517. <https://doi.org/10.5194/tc-14-1497-2020>
- Picard, G., Libois, Q., Arnaud, L., Verin, G., & Dumont, M. (2016). Development and calibration of an automatic spectral albedometer to estimate near-surface snow SSA time series. *The Cryosphere*, 10(3), 1297–1316. <https://doi.org/10.5194/tc-10-1297-2016>
- Ricchiazzi, P., Yang, S., Gautier, C., & Soble, D. (1998). SBDART: A Research and Teaching Software Tool for Plane-Parallel Radiative Transfer in the Earth's Atmosphere. *Bulletin of the American Meteorological Society*, 79(10), 2101–2114. [https://doi.org/10.1175/1520-0477\(1998\)079<2101:SARATS>2.0.CO;2](https://doi.org/10.1175/1520-0477(1998)079<2101:SARATS>2.0.CO;2)
- Robinson, D. A., & Estilow, T. W. (2012). Northern hemisphere snow cover extent dataset. <https://climate.rutgers.edu/snowcover/>

- Robinson, D. A., & Frei, A. (2000). Seasonal Variability of Northern Hemisphere Snow Extent Using Visible Satellite Data. *The Professional Geographer*, 52(2), 307–315. <https://doi.org/10.1111/0033-0124.00226>
- Skiles, S. M., Flanner, M., Cook, J. M., Dumont, M., & Painter, T. H. (2018). Radiative forcing by light-absorbing particles in snow. *Nature Climate Change*, 8(11), 964–971. <https://doi.org/10.1038/s41558-018-0296-5>
- Vaughan, D., Comiso, J., Allison, I., Carrasco, J., Kaser, G., Kwok, R., Mote, P., Murray, T., Paul, F., Ren, J., Rignot, E., Solomina, O., Steffen, K., & Zhang, T. (2013). Observations: Cryosphere. In T. Stocker, D. Qin, G.-K. Plattner, M. Tignor, S. Allen, J. Boschung, A. Nauels, Y. Xia, V. Bex, & P. Midgley (Eds.), *Climate change 2013: The physical science basis. Contribution of working group I to the fifth assessment report of the intergovernmental panel on climate change*. Cambridge University Press.
- Wakahama, G. (1968). The metamorphism of wet snow. *IASH Publ.*, 79, 370–379.
- Warren, S. G., Rigor, I. G., Untersteiner, N., Radionov, V. F., Bryazgin, N. N., Aleksandrov, Y. I., & Colony, R. (1999). Snow Depth on Arctic Sea Ice. *Journal of Climate*, 12(6), 1814–1829. [https://doi.org/10.1175/1520-0442\(1999\)012<1814:SDOASI>2.0.CO;2](https://doi.org/10.1175/1520-0442(1999)012<1814:SDOASI>2.0.CO;2)
- Warren, S. G., & Wiscombe, W. J. (1980). A Model for the Spectral Albedo of Snow. II: Snow Containing Atmospheric Aerosols. *Journal of Atmospheric Sciences*, 37(12), 2734–2745. [https://doi.org/10.1175/1520-0469\(1980\)037<2734:AMFTSA>2.0.CO;2](https://doi.org/10.1175/1520-0469(1980)037<2734:AMFTSA>2.0.CO;2)
- World Meteorological Organization. (2024). Blowing snow. Retrieved May 15, 2026, from <https://cloudatlas.wmo.int/en/blowing-snow.html>